APPENDIX | PRINCIPLES OF THE NEW URBANISM

The Region, Metropolis, City, and Town

- 1. Metropolitan regions are finite places with geographic boundaries derived from topography, watersheds, coastlines, farmlands, regional parks, and river basins. The metropolis is made of multiple centers that are cities, towns, and villages, each with its own identifiable center and edges.
- 2. The metropolitan region is a fundamental economic unit of the contemporary world. Governmental cooperation, public policy, physical planning, and economic strategies must reflect this new reality.
- 3. The metropolis has a necessary and fragile relationship to its agrarian hinterland and natural landscapes. The relationship is environmental, economic, and cultural. Farmland and nature are as important to the metropolis as the garden is to the house.
- 4. Development patterns should not blur or eradicate the edges of the metropolis. Infill development within existing urban areas conserves environmental resources, economic investment, and social fabric, while reclaiming marginal and abandoned areas. Metropolitan regions should develop strategies to encourage such infill development over peripheral expansion.
- 5. Where appropriate, new development contiguous to urban boundaries should be organized as neighborhoods and districts, and be integrated with the existing urban pattern. Non-contiguous development should be organized as towns and villages with their own urban edges, and planned for a jobs/housing balance, not as bedroom suburbs.
- 6. The development and redevelopment of towns and cities should respect historical patterns, precedents, and boundaries.
- 7. Cities and towns should bring into proximity a broad spectrum of public and private uses to support a regional economy that benefits people of all incomes. Affordable housing should be distributed throughout the region to match job opportunities and to avoid concentrations of poverty.
- 8. The physical organization of the region should be supported by a framework of transportation alternatives. Transit, pedestrian, and bicycle systems should maximize access and mobility throughout the region while reducing dependence upon the automobile.
- 9. Revenues and resources can be shared more cooperatively among the municipalities and centers within regions to avoid destructive competition for tax base and to promote rational coordination of transportation, recreation, public services, housing, and community institutions.

The Neighborhood, the District and the Corridor

- 10. The neighborhood, the district, and the corridor are the essential elements of development and redevelopment in the metropolis. They form identifiable areas that encourage citizens to take responsibility for their maintenance and evolution.
- 11. Neighborhoods should be compact, pedestrian-friendly, and mixed-use. Districts generally emphasize a special single use, and should follow the principles of neighborhood design when possible. Corridors are regional connectors of neighborhoods and districts; they range from boulevards and rail lines to rivers and parkways.
- 12. Many activities of daily living should occur within walking distance, allowing independence to those who do not drive, especially the elderly and the young. Interconnected networks of streets should be designed to encourage walking, reduce the number and length of automobile trips, and conserve energy.
- 13. Within neighborhoods, a broad range of housing types and price levels can bring people of diverse ages, races, and incomes into daily interaction, strengthening the personal and civic bonds essential to an authentic community.
- 14. Transit corridors, when properly planned and coordinated, can help organize metropolitan structure and revitalize urban centers. In contrast, highway corridors should not displace investment from existing centers.
- 15. Appropriate building densities and land uses should be within walking distance of transit stops, permitting public transit to become a viable alternative to the automobile.
- 16. Concentrations of civic, institutional, and commercial activity should be embedded in neighborhoods and districts, not isolated in remote, single-use complexes. Schools should be sized and located to enable children to walk or bicycle to them.
- 17. The economic health and harmonious evolution of neighborhoods, districts, and corridors can be improved through graphic urban design codes that serve as predictable guides for change.
- 18. A range of parks, from tot-lots and village greens to ball fields and community gardens, should be distributed within neighborhoods. Conservation areas and open lands should be used to define and connect different neighborhoods and districts.

The Block, the Street and the Building

- 19. A primary task of all urban architecture and landscape design is the physical definition of streets and public spaces as places of shared use.
- 20. Individual architectural projects should be seamlessly linked to their surroundings. This issue transcends style.
- 21. The revitalization of urban places depends on safety and security. The design of streets and buildings should reinforce safe environments, but not at the expense of accessibility and openness.
- 22. In the contemporary metropolis, development must adequately accommodate automobiles. It should do so in ways that respect the pedestrian and the form of public space.
- 23. Streets and squares should be safe, comfortable, and interesting to the pedestrian. Properly configured, they encourage walking and enable neighbors to know each other and protect their communities.
- 24. Architecture and landscape design should grow from local climate, topography, history, and building practice.
- 25. Civic buildings and public gathering places require important sites to reinforce community identity and the culture of democracy. They deserve distinctive form, because their role is different from that of other buildings and places that constitute the fabric of the city.
- 26. All buildings should provide their inhabitants with a clear sense of location, weather and time. Natural methods of heating and cooling can be more resource-efficient than mechanical systems.
- 27. Preservation and renewal of historic buildings, districts, and landscapes affirm the continuity and evolution of urban society.

APPENDIX | PEDESTRIAN ENVIRONMENT ANALYSIS

Walkability Audit - Summary

Prior to the design workshop, Walk Albuquerque and Alliance for Active Living organized a volunteer group to travel and evaluate the pedestrian world in the Central-Highland-Upper Nob Hill area. Three routes on Central, from Carlisle to San Mateo, were evaluated on two different Saturdays. This was a small sampling, with 6-7 people in each group, including area residents, business owners and members of the associations running the volunteer event. Participants familiar with this area noted that Saturday activity varies from weekday activity.

This type of analysis helped inform the design team as to the current state of affairs for the pedestrian, which is directly linked with the success of businesses in the area. A comment by one participant summed up the existing condition of the area for both folks on foot and for businesses in the area:

"I didn't think about the businesses at all. You just paid attention to the cars." (and the ground in front of your feet.)

Tally sheets with various criteria were given to participants. Results were tallied and the following general issues arose:

- · Traffic: noise, fumes, speed, no buffer between sidewalk and cars in many places.
- Driver behavior: failure to yield to pedestrians, especially when turning.
- · Sidewalks: broken sidewalks, rough surfaces, frequent driveways with steep side slopes, utility poles and other obstacles blocking the way. Very steep curb ramps that send walkers out into the traffic flow, uneven joints. Sidewalks too narrow to walk two abreast and pass anyone. No buffer between sidewalks and traffic lanes in many places.
- · Street Crossings: timing on pedestrian crossing signals too short, intersections too wide, no really useful median refuges, parked cars block views at some intersections.
- · Safety (real or perceived): barred windows, vacant lots, vast parking lots, vacant stores, locked front doors facing Central with signs to go around the back or side, no loitering signs, few other pedestrians out - of those we saw, some were perceived of as "scary".
- · Buildings and land use: Many buildings are designed for cars, with large parking lots facing Central along the sidewalk, multiple driveways crossing sidewalks, entrances oriented to parking lots, rather than sidewalks. The block west of the Highland theater was the worst in total lack of pedestrian accommodations.
- Many vacant parcels and vacant buildings
- Vast no man's land south of the theater, and around Highland High School
- Very little residential within the MRA boundaries
- Highland Theater is a definite positive, as well as a few other isolated and short segments, where businesses with interesting facades were close to the sidewalk and onstreet parking provided a buffer for pedestrians.
- · Aesthetics and amenities: dirt, litter, graffiti, few trees, benches, trash receptacles, etc.
- · Central has an active bus route, but bus stops generally lacked amenities. Few benches (standard issue grey recycled plastic) or trash receptacles, no shade or shelter.
- · We weren't considering bicycles with this audit, but we noted several bicycles competing with pedestrians for space on narrow sidewalks, and no bike parking facilities.

















ROUTE #2: Your starting Day & date: Start time		n is the End time:	northeast o	corner of Monro Weather:	e & Copper
2/1/04 Sot. 9:40	*	10:45		cold clean	
Segment #1: Cross to the so	uth side	of Coppe	er, staying	on the east sid	e of Monroe
How difficult or easy was it to cro	ss the stre	et at this	location? (please check only	one)
	Somewhat	, NO	Somewhat eas	y /□ Very easy	$\ \square$ Extremely easy
difficult difficult	difficult				
How safe did you feel crossing th					
☐ Extremely ☐ Very ☐ unsafe unsafe	Somewhat unsafe	11)11	Somewhat saf	e // 🗆 Very safe	☐ Extremely safe
If you experienced problems crossing		nleace in	dicata which (types (check all tha	t anniv):
If you experienced problems crossing Getting from Sidewalk to the Street:	g the street,		Other:	types (check all tha	с арріу).
Curb ramp(s) not available				ian crossing signal	
Curb ramp(s) not in line with sidewa	lk		☐ Long wait a		
Curb ramp(s) lead into active auto to	avel lane		☐ Pedestrian	push button is difficul	t to find/ hard to reach
☐ Curb ramp(s) too steep			☐ Pedestrian	push button on traffic	signal does not work
□ Level landing not available at top of	curb ramp(s)		∫ Curbed me	dian refuge is not ava	ilable
	et is rough/ u	neven		s block view of traffic	
In the Street:				uctions block view of	traffic
If the Street. If □ Crosswalk is not marked			Other:_/_		affic on Copper
□ Pavement is rough or uneven					ON Monroe is
☐ Roadway is too wide				WISI	With .
☐ Traffic signal does not give enough	time to cross			-nothin	atalslow traff
 Drivers fail to yield to pedestrians in 	crosswalk			1e. Stop	sigms, as fow
□ Drivers don't look for pedestrians w	nen making tu	irns		as eve	coln sée
				- IN DUA	locationy
				not anto	raw had to ba
					teep curb
				- Veru li	and two Atre
					ghit traffic years diam'ty
				-twner	gears alom + 4
					J

Sample score cards used by walkability volunteers

	Central, from Monroe to San Mateo
Dverall, how pleasant was your walk over this segment of the learning of the l	he route? (please check only one)
f you were alone, how safe would you feel walking here du	ring the day? (please check only one)
	fe IM Somewhat I Very Extremely safe safe safe
What sorts of things did you like walking along this segmen	t? (check all that apply)
□ People met or passed along the way □ Friendly dogs/ cats □ Businesses / shop widows (□ Businesses / shop prizement Hew Chunch Pend	/□ Trees along sidewalk or pathway □ Paving materials/ patterns of sidewalk or pathway □ Other: SUM Shune □ INCYEA SE IN VENTALS - ST
What sorts of things did you NOT like? (check all that apply	
Oirty sidewalk	HT Not enough trees or other vegetation HT Not enough shelter from sun, rain, wind, etc. HT No place to sit (e.g., benches, etc.) HT Traffic too close to sidewalk HT Traffic moves too fast HT Traffic noise HT Vehicle exhaust furnes Other: Deand HE Deangle HT Ages Ages Indicate the types of obstacles or obstructions
	nor-Road Intersections:
Sidewalk is too narrow	Curb ramp(s) not available Curb ramp(s) not in line with sidewalk Curb ramp(s) lead into active auto travel lane Curb ramp(s) too steep Level landing not available at top of curb ramp(s) Transition from curb ramp(s) to street is rough/ uneven Rough or uneven street pavement
Alfohou manin on the side	Other: Cay's not yielding to peds
	alle - especially unsighely
	ported news
· Ho tench or shorts at bus stop · businesses not open during · comers especially difficult i	

















APPENDIX | TRAFFIC ANALYSIS

Traffic Considerations:

The focus of the Street and sidewalk designs are to slow traffic down while increasing capacity of traffic volume on Central Ave.. The safety and aesthetics of the pedestrian environment [and also the economic environment] should be as important as the considerations given to vehicles in the area, if not more so. Some parameters of the design:

- 1. Pedestrian crossing times must be kept to a minimum. Crossing times of 19 seconds or less are preferred. This represents a street with four 12 foot wide lanes.
- 2. Vehicle speeds must be kept to 20 miles per hour or less generally, and around 30 miles per hour on primary thoroughfares.
- 3. Pedestrians should be protected from the elements as much as practical.
- 4. Streets should be defined by buildings at their edges.
- 5. The street must accommodate bicyclists and the handicapped.
- 6. Transit must be a part of thoroughfare planning.
- 7. Parking standards must be reduced to reflect historically supported demand for traditional urbanism.
- 8. Central is the main artery for the project and needs special attention.

The design of Central Avenue is informed by several elements listed as follows;

- 1. A LRT or BRT system may be introduced into the corridor. This would require a 26 foot wide path in the center of the street. To allow for this potential, a 26 foot wide median is proposed as one of the cross section scenarios.
- 2. The intersection of Central and San Mateo is operating at LOS F with more than 4,000 vehicles at PM peak hour times. This study proposes that a 2 lane roundabout be built in the intersection. This will provide better access for non-motorists, boost the LOS to B, reduce accidents and will allow some civic art in the center punctuation this area of the neighborhood. See traffic model output in later pages this appendix.
- 3. The other signalized intersections along Central operate in the low to mid 30,000 ADT range. For the above stated reasons, each intersection could have a single lane roundabout with 2 approach lanes and one exit lane. The LOS would be B and they would upgrade existing signal performance characteristics. Samples of possible design for two intersections are illustrated as follows:

It should be noted that the 26 foot wide median is shown at Washington, but not San Mateo. An 18 foot increase to the median width can be achieved and work well with a 2 lane roundabout.

Slower traffic speeds are critical for safety in this corridor. A combination of on-street parking, narrower street designs, bulb-outs, street trees, and roundabouts are proposed to keep traffic at posted speeds throughout the area. The following table shows in graphic detail the repercussions of pedestrian/automobile collisions as they relate to automobile speed:

Selected Sample of Injuries by the Abbreviated Injury Scale (AIS) AIS Code Injury Severity Level and Selected Injuries

- 1 (14 mph) Minor Superficial abrasion or laceration of skin; digit sprain; first-degree burn; head trauma with headache or dizziness (no other neurological signs).
- 2 (20 mph) Moderate Major abrasion or laceration of skin; cerebral concussion (unconscious less than 15 minutes); finger or toe crush/amputation; closed pelvic fracture with or without dislocation.
- 3 (25 mph) Serious Major nerve laceration; multiple rib fracture (but without flail chest); abdominal organ contusion; hand, foot, or arm crush/amputation.
- 4 (29 mph) Severe Spleen rupture; leg crush; chest-wall perforation; cerebral concussion with other neurological signs (unconscious less than 24 hours).
- 5 (33 mph) Critical Spinal cord injury (with cord transection); extensive secondor third-degree burns; cerebral concussion with severe neurological signs (unconscious more than 24 hours).
- 6 (36 mph) Fatal Injuries which although not fatal within the first 30 days after an accident, ultimately result in death.


WTP Values Per AIS Injury Level (2001 dollars) AIS Code Description of Injury Fraction of WTP Value of Life WTP Value

AIS 4 Severe 18.75 Percent \$562,500 AIS 5 Critical 76.25 Percent \$2,287,50	AIS 1 Minor	0.20 Percent	\$6,000
AIS 4 Severe 18.75 Percent \$562,500 AIS 5 Critical 76.25 Percent \$2,287,50	AIS 2 Moderate	1.55 Percent	\$46,500
AIS 5 Critical 76.25 Percent \$2,287,50	AIS 3 Serious	5.75 Percent	\$172,500
	AIS 4 Severe	18.75 Percent	\$562,500
AIS 6 Fatal 100.00 Percent \$3,000,0		76.25 Percent	\$2,287,500
	AIS 6 Fatal	100.00 Percent	\$3,000,000

As can be seen, the costs increase exponentially with speed. Tax dollars are spent every year to treat uninsured accident victims and the fiscal costs are sometimes excessive.



Narrow lanes, transit mixed in traffic, wide sidewalks



Balancing people and cars in an environment

APPENDIX | TRAFFIC ENGINEERING SIDRA ROUNDABOUT OUTPUT

(ENTRAL AND WASHINGTON	
	Degree of saturation (highest)	= 0.636
	Practical Spare Capacity (lowest)	= 34 %
	Total vehicle flow (veh/h)	= 3369
	Total vehicle capacity, all lanes (veh/h)	= 5995
	Average intersection delay (s)	= 14.2
	Largest average movement delay (s)	= 32.4
	Total vehicle delay (veh-h/h)	= 13.26
	Largest back of queue, 95% (ft)	= 169
	Performance Index	= 56.50
	Intersection Level of Service	= B
	Worst movement Level of Service	= C

SAN MATEO AND CENTRAL	
Degree of saturation (highest)	= 0.861
Practical Spare Capacity (lowest)	= -1 %
Total vehicle flow (veh/h)	= 5233
Total vehicle capacity, all lanes (veh/h)	= 7039
Average intersection delay (s)	= 17.1
Largest average movement delay (s)	= 20.3
Total vehicle delay (veh-h/h)	= 24.91
Largest back of queue, 95% (ft)	= 264
Performance Index	= 108.27
Intersection Level of Service	= B
Worst movement Level of Service	= C

Akcelik & Associates Pty Ltd - SIDRA 5.30	
Swift and Associates	
Longmont Registered User No. LKWHEF	
Time and Date of Analysis 3:49 PM, Feb 27,2004	
Central Na Washington, ABQ	* CENWASPM
PM Peak Hour	
Intersection ID: 1	
SIDRA US Highway Capacity Manual Version	Roundabout
RUN INFORMATION	
* Basic Parameters:	
Intersection Type: Roundabout	
Driving on the right-hand side of the road	
SIDRA US Highway Capacity Manual Version	
Input data specified in US units	
Default Values File No. 11	
Peak flow period (for performance): 15 minutes	
Unit time (for volumes): 60 minutes (Total Flow Perio	od)
Delay definition: Control delay	
Geometric delay included	
Delay formula: Highway Capacity Manual	
Level of Service based on: Delay (HCM)	
Queue definition: Back of queue, 95th_Percentile	

No.				-	_		Flow Scale	
	LV	HV					Scale	
West: West Appr	oach							
	91			24	42	1	1.00	0.90
South: South App								
32	33	1	266	5	63	1	1.00	0.90
East: East Appro	ach							
			-		25	, 1	1.00	0.90
North: North Ap								
42	52	1	279	6	84	2	1.00	0.90

Cont Circ 1	Av Ent	Circulating/Exiting Stream						
Cent Circ Insc No.of No.of Island Width Diam. Circ. Entr Diam Lanes Lan (ft) (ft) (ft)		Entry Lanes	Lane	Flow (veh/	%HV	Adjust. Flow (pcu/h)	Incl.	Constr
 West: West Ap	oroach							
64 20 10				421				
South: South A								
64 20 104	1	2	16.00	1399	2.0	1399	0	N
East: East Appr	oach							
64 20 104				98				
North: North A								
64 20 104	1	2	16.00	1194	2.0	1194	0	Ν

Central Na Washington, ABQ	* CENWASPM
PM Peak Hour	
Intersection ID: 1 Roundabout	

Table R.1 - ROUNDABOUT GAP ACCEPTANCE PARAMETERS

Turn	Lane No.	Lane Type	Circ/ Exit Flow (pcu/h)	Bunch Headway		Gap	Follow Up Headway (s)
West:	West	Approach					
Left	1	Dominant	421	2.00N	0.443	3.17	2.04
Thru	1	Dominant	421	2.00N	0.443	3.17	2.04
	2	Subdominant	421	2.00N	0.443	3.69	2.38
Right	2	Subdominant	421	2.00N	0.443	3.69	2.38
South	 n: Sou	th Approach					
Left	1	Subdominant	1399	2.00N	0.857	2.94	2.25
Thru	1	Subdominant	1399	2.00N	0.857	2.94	2.25
	2	Dominant	1399	2.00N	0.857	2.41	1.85
Right	2	Dominant	1399	2.00N	0.857	2.41	1.85
East:	 East <i>F</i>	 Approach					
Left	1	Dominant	398	2.00N	0.424	3.21	2.06
Thru	1	Dominant	398	2.00N	0.424	3.21	2.06
	2	Subdominant	398	2.00N	0.424	3.72	2.39
Right	2	Subdominant	398	2.00N	0.424	3.72	2.39
North	n: Nor	th Approach					
Left	1	Subdominant	1194	2.00N	0.810	3.00	2.30
Thru	1	Subdominant	1194	2.00N	0.810	3.00	2.30
	2	Dominant	1194	2.00N	0.810	2.52	1.93
Right	2	Dominant	1194	2.00N	0.810	2.52	1.93

N The number of circulating lanes specified in front of this approach ("No. of circ. lanes" in Roundabout Data screen) is less than the number of lanes effectively used when the entry flows that constitute the circulating flow are considered. Intra-bunch headway for the circulating stream has been set to a higher value as a result.

	SIDRA	HCM Lower	HCM Upper
Mov Arv No. Flow (veh /h)	Cap. Deg. Av.	(veh Satn Delay LOS	Cap. Deg. Av. (veh Satn Delay LOS /h) x (sec)
West: West Appr	oach		
12 LTR 1388	2264 0.613 10.9 B	1617 0.858 19.4 B	1988 0.698 13.4 B
	2264 0.613 10.9 B	1617 0.858 19.4 B	1988 0.698 13.4 B
South: South Ap	proach		
32 LTR 369	580 0.636 32.4 C	· NA	NA
	580 0.636 32.4 C	· NA	NA
East: East Appro	ach		
22 LTR 1188	2287 0.519 10.0 A	1650 0.720 14.4 B	2025 0.587 11.5 B
	2287 0.519 10.0 A	1650 0.720 14.4 B 2	025 0.587 11.5 B
North: North Ap	proach		
42 LTR 424	864 0.491 20.8 C	808 0.525 32.6 C	1060 0.400 26.2 C
	864 0.491 20.8 C	808 0.525 32.6 C	1060 0.400 26.2 C
ALL VEHICLES:	5995 0.636 14.2 B	NA	NA

NA Values for this roundabout capacity model have not been calculated because the model was not applicable for the given roundabout conditions. Note that the HCM models are only applicable to singlelane roundabouts with circulating flows less than 1200 veh/h. Also note that results are not calculated for any of the models for slip lane or continuous movements. See SIDRA Output Guide Appendix Section A3.8 for roundabout limits.

Mov No.	Flow	Opng			Cap.	Deg.	•		- 6
(veh Flow /h) (veh/h)				`	Satn xp		(%)	х	
West: W	/est Ap	proach							
	-				•	0.85			-
		Approacl							
32 LTR	369	1399	2.0	1399	580	0.85	34	100	0.636*
East: Ea	ıst App	roach							
22 LTR	1188	398	2.0	398	2287	0.85	64	100	0.519
North:	North /	Approacl	 1						
42 LTR	424	1194	2.0	1194	864	0.85	73	100	0.491

Client: City of Albuquerque Planning Department Albuquerque, New Mexico

Degree of saturation (highest)	=	0.636
Practical Spare Capacity (lowest)	=	34 %
Total vehicle flow (veh/h)	=	3369
Total vehicle capacity, all lanes (veh/h)	=	5995
Average intersection delay (s)	=	14.2
Largest average movement delay (s)	=	32.4
Total vehicle delay (veh-h/h)	=	13.26
Largest back of queue, 95% (ft)	=	169
Performance Index	=	56.50
Total fuel (ga/h)	=	29.7
Total cost (\$/h)	=	266.67
Intersection Level of Service	=	В
Worst movement Level of Service	=	C

Table S.5	- MOVEME	NT PERFO	DRMANCE					
Mov No.	Total Delay (veh-h/h)	Delay	Prop. Queued	Eff. Stop Rate		,	Perf. Index	Aver. Speed (mph)
West: We	est Approac	:h						
12 LTR	4.20	10.9	0.59	0.77	5.6	143	19.83	16.5
South: So	outh Appro	ach						
32 LTR	3.32	32.4	0.91	1.34	6.7	169	11.72	9.1
East: Eas	t Approach	1						
22 LTR	3.29	10.0	0.53	0.70	3.8	97	15.54	16.8
North: N	orth Appro	ach						
42 LTR	2.45	20.8	0.85	1.10	4.1	104	9.40	12.0

Mov No.		Delay	Prop. Queued	Stop	Longest (95% Back (vehs)			Aver. Speed (mph)
West: We	est Approa	 ch						
12 LTR	4.20	10.9	0.59	0.77	5.6	143	19.83	16.5
South: S	outh Appro	 ach						
32 LTR	3.32	32.4	0.91	1.34	6.7	169	11.72	9.1
East: Eas	st Approach	 1						
22 LTR	3.29	10.0	0.53	0.70	3.8	97	15.54	16.8
North: N	Iorth Appro	ach						
42 LTR	2.45	20.8	0.85	1.10	4.1	104	9.40	12.0

Table S.6	- INTERSE	CTION PE	RFORMAN	CE		
Flow	Total Delay (veh-h/h)	Delay		Stop	Index	
West: W	est Approa	 ch				
-	4.20	-				-
	outh Appro					
	3.32		-		•	9.1
	st Approach					
1188	3.29	10.0	0.532	0.70	15.54	16.8
North: N	North Appro	 oach				
	2.45		-			
INTERSE	CTION:					
3369	13.26	14.2	0.639	0.85	56.50	14.6

		Arv Flow	Сар	Deg.	Aver.	Eff.	Q u e u e 95% Back	Short
Lane	Mov	(veh	(veh	Satn	Delay	Stop		Lane
No.	No.	/h)	/h)	Х	(sec)	Rate	(vehs) (ft)	(ft)
West:	West App	roach						
ı LT	12	757	1235	0.613	10.6	0.74	5.6 141	
2 TR	12	631	1028	0.613	11.2	0.79	5.6 143	
South	: South A	pproach						
ı LT	32	158	249	0.636	34.6	1.31	5.6 143	
2 TR	32	211	332	0.636	30.7	1.36	6.7 169	
East:	East Appr	 oach						
ı LT	22	646	1244	0.519	9.8	0.69	3.8 97	
2 TR	22	542	1044	0.519	10.1	0.72	3.7 95	
North	: North A	pproach						
ı LT	42	187	381	0.491	22.3	1.10	3.7 94	
2 TR	42	237	483	0.491	19.7	1.10	4.1 104	

Lan	Mov	` , ,		Saturation Flow Adj. Aver Aver	•	Сар	•	
No.	No.			Basic 1st 2nd (tcu) (veh) (veh)	•	•		
West:	: West App	roach						
ı LT	12	93 664 0 757	16.0N		60	1235	0.613	100
		0 588 43 631					-	
	n: South Ap	pproach						
ı LT	32	34 124 0 158	16.0N		60	249	0.636	100
2 TR	32	0 147 64 211	16.0N		60	332	0.636	100
East:	East Appro	oach						
ı LT	22	84 562 0 646	16.0N		60	1244	0.519	100
		0 516 26 542			60	1044	0.519	100
	n: North A	 pproach						
ı LT	42	53 134 0 187	16.0N		60	381	0.491	100
2 TR	42	0 151 86 237	16.0N		60	483	0.491	100

N Width value was not used for saturation flow adjustment in this case. (Lane width adjustment does not apply at sign-controlled intersections or to gap-acceptance capacities at signalised intersections).

Basic Saturation Flow in this table is adjusted for lane width, approach grade, parking manoeuvres and number of buses stopping. Saturation flow scale applies if specified.

Lane Arrival Flow (veh/h) No % L T R Tot		Adj. Eff Grn Deg Basic (secs) Sat Satf. 1st 2nd x	Delay	Queue	Lane
 West: West Approach					
::	2	0.688	15.6	140	
T 0 410 0 410	2		15.5		
TR 0 276 134 410	2	0.688			
230 934 134 1298	2	0.688	15.4	140	
South: South Approach					
LT 188 278 O 466	2	0.685	14.9	126	
T o 395 o 395	2	0.685	15.0	118	
TR o 261 134 395	2	0.685			
188 934 134 1256	2	0.685	14.8	126	
East: East Approach					
LT 341 240 0 581	2	0.860			
10 10	2	0.860		243	
TR 0 283 208 491	2	0.860	19.7	243	
341 1015 208 1564	2	0.860	20.2	264	
North: North Approach					
LT 174 172 O 346	2	0.744			
T o 346 o 346	2		18.0		
TR 0 227 195 422	2	0.744	16.1	154	

174 746 19	5 1115	2	0.744	17.6	154	
ALL VEHICLES	Tot	%	 Max	Aver.	Max	
	Arv.	HV	X	Delay	Queue	
	5233	2	0.861	17.1	264	

Note: Basic Saturation Flows are not adjusted at roundabouts or signcontrolled intersections and apply only to continuous lanes. Values printed in this table are back of queue.

Mov Mov	Total	Total	Deg.	Aver.	LOS	
No. Typ	Flow	Cap.	of	Delay		
	(veh	(veh	Satn			
	/h)	/h)	(v/c)	(sec)		
West: West Approa	 ach					
12 L	230	334	0.689	15.6	В	
11 T	934	1358	0.688	15.4	В	
13 R	134	195	0.687	15.0	В	
	1298	1887	0.689	15.4	В	
South: South Appr	roach					
32 L	188	275	0.684	14.9	В	
31 T	934	1364	0.685	14.8	В	
33 R	134	196	0.684	14.4	В	
	1256	1835	0.685	14.8	В	
East: East Approac	 ch					
22 L	341	396	0.861*	20.3	C	
21 T	1015	1180	0.860	20.2	C	
23 R	208	242	0.860	19.7	В	
	1564	1818	0.861	20.2	C	
North: North Appı	roach					
42 L	174	234	0.744	19.0	В	
41 T	746	1003	0.744	17.7	В	
43 R	195	262	0.744	16.1	В	
	1115	1499	0.744	17.6	В	
ALL VEHICLES:	5233	7039	0.861	17.1	В	
INTERSECTION:	5233	7039	0.861	17.1	 В	

Level of Service calculations are based on average control delay including geometric delay (HCM criteria), independent of the current delay definition used. For the criteria, refer to the "Level of Service" topic in the SIDRA Output Guide or the Output section of the on-line help.

* Maximum v/c ratio, or critical green periods

		Dela									
Lane Control	Mov	Deg. Satn					Queuir Total M	ng NvUp	Stopd (Idle) Geom		
No.	No.	х	dι	d2	dSL	dn	dq	dqm	di	dig	dic
West: \	 West Appr	oach									
ı LT		0.688	4.7	2.4	7.1	3.7	3.4	3.3	0.1	9.6	15.6
2 T	11 11	0.688	5.3	2.5	7.6 7.9	3.7	4.2	3.3	0.9	7.6	15.
3 TR								3.3			_
	13				6.1						
South:	South Ap	proach									
ı LT		0.685	4.4	2.1	6.5	3.5	2.9	2.9	0.0	9.6	14.
2 T	31 31	0.685	5.0	2 2	7.6 7.2	3.6	3.7	2 2	0.6	7.6	15 (
3 TR	31,	0.685	5.0				3.7		0.6	7.6	_
,	33		,		6.1	,	,	,		,	Ċ
East: E	ast Appro	ach									
1 LT		0.860	5-3	6.3		3.9	7.6	7.6	0.1	9.6	20.
2 T	21	0.960	6.0	6.9	7.6		0 -			- 6	
		o.86o o.86o					8.7		1.3 1.3		
) IN	23	0.000	0.0	0.0	6.1	4.0	0.7	7.5	1.5	7.0	19.
North:	North Ap	proach									
ı LT		0.744	6.4	4.0	10.4	3.9	6.5	4.8	1.7	9.6	19.
_	41				7.6		_				_
2 T		0.744					6.5		1.7		
3 TR	41, 43	0.744	5.5	3.7	9.2 6.1	3.8	5.4	4.9	0.5	7.6	16

dn is average stop-start delay for all vehicles queued and unqueued

Table [_		•									PM P	l and San Ma eak Hour, City	Data		CENSA	NPM
													ection ID: 1 dabout				
Queue																	
No.	х	No	Nbı	Nba	Nb	70%	85%	909	6 95%	6 98%		Table	D.4 - MOVEN	IENT SPEEDS	(mph)		
West:														(Queue Move-up)	
						3.2						١		Exit Speeds			
	0.688	0.5	1.0	0.7	1.7	3.0 3.0	3.7	4.2	5.2	6.0	0.44	No.	Cruise Negn	Negn Cruise			
South													: West Appro				
ı LT o	0.685	0.4	1.0	0.6	1.6	2.9	3.5	4.0	4.9	5.8	0.42	12	28.0 14.0	14.0 28.0			
2 T (.685	0.4	0.9	0.6	1.5	2.7	3.3	3.7	4.6	5-4	0.39			14.0 28.0		14.7	14.4
						2.7						13	28.0 14.0	14.0 28.0	10.6	14.8	14.3
East:												South	h: South App	roach			
1 LT (.860	1.4	1.4	2.2	3.5	5.8	7.2	8.3	10.4	12.2	0.88	32	28.0 14.0	14.0 28.0	10.9	14.9	14.9
						5-4						_		14.0 28.0	-	14.9	14.7
						5.4							28.0 14.0	14.0 28.0	10.4	14.9	14.6
North													East Approa				
1 LT (.744	0.6	0.9	0.9	1.8	3.2	3.9	4.4	5.5	6.4	0.47	22	28.0 14.0	14.0 28.0		12.9	
2 T (.744	0.6	0.9	0.9	1.8	3.2	3.9	4.4	5-5	6.4	0.47	21	28.0 14.0	14.0 28.0	10.5	12.8	12.5
3 TR	0.744	0.6	1.0	1.0	2.0	3.5	4.3	4.9	6.1	7.1	0.51	23	28.0 14.0	14.0 28.0	10.4	12.7	12.2
/alues	printe	ed in t	his ta	ble a	re ba	ck of qu	eue.					Nort	h: North App	roach			
												42	28.0 14.0	14.0 28.0	10.0	14.0	13.3
														14.0 28.0		13.9	13.4
												43	28.0 14.0	14.0 28.0	10.6	13.9	13.7

END

